Product Name:	KVP-4 CS
December	A DC 1/m review lift Corpto are
Description:	ABS Kryovault System Auto Fill Tank
	Stainless steel outer & inner tank wrapped with super insulate
	(5) lockable casters
	Hinged lid with locking provision
	(2) foldable skid free steps
	Inner aluminum inventory carousel
	6 ft. armor plated transfer hose
	Fully operational battery back-up
	Sentry plus controller
	Sentry Plus Auto-Fill Controller features:
	Power-Guard battery back up
	Freeze-Guard overfill protection
	Quick-chill temperature recovery
	Auto-defog visibility safety
	Splash-Guard false alarm prevention
	Help button, user assistance
	<ul> <li>System log, alarm log, and temperature log with total 500,000</li> </ul>
	events
	Serial port, 2 way communications
	• 4-20mA port
	Ready for icSmart remote monitoring system
	Keyless entry to power and control settings
	Audio and visual alarms:
	High temperature     High flow LNO level.
	High/low LN2 level     Valve stuck open
	Valve stuck open     Lid open
	<ul><li>Lid open</li><li>Power failure</li></ul>
	Sensor failure
	Low LN2 supply
	<ul> <li>Unauthorized access</li> </ul>
	<ul> <li>Usage warning</li> </ul>
	<ul> <li>Temp calibration</li> </ul>
	<ul> <li>Low battery</li> </ul>
	<ul> <li>LN2 level readout +/- 1" (direct sensor LN2 contact)</li> </ul>
	LN2 supply monitor
	LN2 usage calculation
	Thermocouple auto-calibration
	Temperature control
	Digital temperature display
	Temp display units: C, F, K, R
	Automatic filling
	Diagnostics at start-up

- Maintenance reminder
- 8 thermistor array

Model specifications:

Total vial capacity (2ml): 94,500

Total bag capacity: 2,304

LN2 capacity (liters / vapor phase): 300

Total LN2 capacity (liters): 1,595 Static evaporation rate (liters/day): 15

Overall height (in/mm): 62/1575
Reach over height (in/mm): 40/1016
Usable height (in/mm): 35.3/896.6
External diameter (in/mm): 59.5/1511
Internal diameter (in/mm): 55/1397
Neck diameter (in/mm): 24.5/622
Weight empty (lbs/kg): 1700/771
Weight full (lbs/kg): 4600/2060

Shipping weight (lbs/kg): 2,250/1020.6

Input Voltage: 120 V

Input Current (Max): 1.75 Amp Input Current (Continuous): 0.5 Amp

Frequency: 50/60 Hz

Three year parts and labor warranty

Five year vacuum warranty **Package System Includes:** 

(60) 15-2 Tower Racks

(900) 81/100 Cell Fiberboard Boxes (8)

15-2 Mini Tower Racks (120) 25 Cell Mini Boxes